HASSAN DISTRICT.

Notice, dated 2nd June 1899.

It is hereby notified that the sales of arrack and toddy shops of the Arsikere taluk have been postponed to 20th June 1899 instead of the 9th as published in Government Notifications Nos. 6570—Ex. 253 and 6719—Ex. 259, dated 18th and 24th March 1899, respectively.

D. DEVARAJ URS, *Dy Comr.*

KOLAR DIVISION.

The 22nd May 1899.

Notice is hereby given that sealed tenders will be received at the office of the Executive Engineer, Kolar division, up to 20th June 1899 (inclusive) for restoring Belluti tank, Registered No. 33, Sidlaghatta taluk. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of June 1900.

2. The plans, detailed estimate, and conditions may be seen at the Executive Engineer's office at Kolar between the hours of 11 A. M. and 5 P. M.

3. Tenders should be submitted on printed forms which may be obtained from the Executive Engineer, and accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed.

4. Each tender must be accompanied by a deposit of Rs. 100 in cash or Government Promissory Notes as earnest money, and be superscribed "Tender for restoring Belluti tank, Registered No. 33, Sidlaghatta taluk," in default of which, tenders will be rejected.

5. The final acceptance of any tender will rest with the Superintending Engineer, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond; in default of which, his tender will be considered cancelled, and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the notice board in the Executive Engineer's office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

Approximate estimate of quantities of work required for restoring Belluti tank, Registered No. 33, Sidlaghatta taluk.

Items of work.	*Per.*	*Quantity.*
Bund 56·00—		
Earthwork	C. yds.	* 13,064
Turfing	S. yds.	9,066
B. M. and registered No. stones	L. S.	Rs. 6
Grade stones	No.	40
Old stone work	C. yds.	461
New stone work (laterite)	„	1,976
Sluices No. 1 and 2—		
Cutting bund	L. S.	Rs. 80
Earthwork excavation	C. yds.	28
Burnt brick in surki mortar	C. ft.	1,262
Do stone slabs	S. ft.	432
Cutting orifice stone with rod and plug, &c.	L. S.	Rs. 20
Chunam plastering	Sqrs.	12·48
Guage stone	L. S.	Rs. 30
Waste weir 150′ long—		
Earthwork	C. yds.	363
Brick in surki mortar	C. ft.	1,968
Plastering, rough	Sqrs.	10·07
Do nice	„	11·05
Slabs	S. ft.	619
Rough stone work, sujicut	C. yds.	432
Do stone wing wall	„	18

* Earthwork will be done by raiyats.

N. ARUNACHELLAM MUDALIAR, *Exec. Engineer.*